BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of work: Providing new pipeline and repairs to existing pipelines in ward no.07 byatarayanapura, kodigehalli Subdivision

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	26.1	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. (P-264, It-37.38)	Cum	360.4	
2	39.15	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Cement Concrete road. (P-257, It-37.40)	Cum	643.42	
3	156.6	KSRB 2-2.2: Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually(other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff levelled and neatly dressed, disposed earth to be levelled and exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed as per specifications. ***(P-5, It,-2.1)***	Cum	166.42	
4	1160	Providing and fixing Chorinated Poly Venyl Chloride(CPVC) pipes confirming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass treaded fittings including fixing the pipe with clamp at 1.oo m spacing.This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete (inertnal work exposed on wall).***PRED SR 2016-17(P-231, Item No.15mm nominal OD PIPES)*** *63mm dia of 6Kg/Cm2*	m	121.9	
5	104.4	KSRB 2.4: Refilling available earth around the pipe lines, cables in layers not exceeding 20 cms in depth , compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications.***PRED SR 2016-17 (P-155, Item No.2.11)***	cum	64.66	
6	221.85	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 ***(P-144 & 150 It.No. 17.1)***	cum	106	
7	78.3	KSRB 4-1.3:Providing and laying position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications. Specification No.KBS 4.1, 4.2 ***(P-12. It.4.3)***	cum	5159.02	

8	52.2	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size grader granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 15 cms. thick well compacted, in ***foundation, plinth and cills,*** *including cost of all materials, labour, HOM of machinary, curing complete as per specifications. Specification No. KBS 4.1, 4.2,* ***(P-12, It;4.5)***	Cum	5874.52	
9	20	KSRB 13-6.2-2: Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.2/13.3***(P-91, It.No.13.27)***	NOS	169.6	
10	20	KSRB 13-6.3-7: Providing and fixing in position brass gate valve with C.I.wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3, ***(P-92, It.No.13.37)***	NOS	2175.12	

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

23/07

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

DTS Approved

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.